

# ADDENDUM NO. 1



SACCOCCIO & ASSOCIATES  
ARCHITECTS

1085 Park Avenue, Cranston, RI 02910 ■ T 401.942.7970 F 401.942.7975 ■ www.sa-architects.com

Project: University of Rhode Island  
Quinn Hall  
CHS Office Space Renovation  
55 Lower College Road  
Kingston, RI 02881

Date: March 25, 2026

## Clarifications regarding the scope of work:

1. Asbestos abatement of existing kitchenette countertop will be completed by the owner prior to the start of construction and is no longer in the scope of work
2. Existing Breakers are Square D
3. Existing card readers:
  - a. Card reader in corridor 226 at entry to 215 shall be salvaged and reinstalled at new location Capture and extend existing cabling. Coordinate all work the Owner's security/access control vendor."
  - b. Card reader inside room 215 will be salvaged and returned to the owner.
4. New door actuators
  - a. Provide 120V power source and cabling to wall mounted pushbuttons as required by manufacturer. Utilize nearest 20A, 120V branch circuit made available by demolition (confirm in field).
5. The height to the existing concrete deck is approximately 12'-0" – 12'-6" AFF but needs to be field verified by the general contractor
6. All new doors are to have hollow metal frames and are to be painted SW 7064 Passive
7. All new full light wood doors are to be maple and stained to match laminate Formica 9041 Natural Refined Hickory